



Aspects of the ICHcompliant Storage

for Stability Tests

Speaker: Dipl.-Ing. Volker Rubarth

Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 1 / 45

RUMED

(())

INDEX



1 Product Selection: Requirements Specification / Functional Specification

2 Qualification: From the DQ to the PQ

3 Operation: Monitoring and Failure Management




Requirements Specification / Functional Specification

Selection of Suitable Products

- Dualism Requirements Specification- Functional Specification
- The Requirements Specification:
 WHAT and FOR WHAT shall something be done?
- The Functional Specification: WHAT and WITH WHAT shall something be realized?







RUME

Rubarth Apparate GmbH

Requirements Specification:

- URS = User Requirements Specification "...requirements stipulated by the principal concerning the deliveries and performances of a contractor"
- Requirements specification
- Preparation by the principal
- Use for tender and forwarding to possible suppliers

- As general as possible and as restrictive as necessary
- The contractor shall develop optimal solutions too precise requirements are restrictive
- Verifiable performances for the formal approval



Structure of the Requirements Specification:

- Introduction/General
- Requirement Profile
- Technical Details:
 - Required Volume
 - Maintenance air circulation in loaded condition for temperature distribution and humidity distribution (PQ) in space
 - Dimensions of the samples (important for existing boxes)
 - Consideration of the weights, particularly in case of liquid forms (reinforced shelves)

A bad example for a requirements specification was:

- Please offer a climatic test cabinet for the stability test
- It shall have a big volume

In this case, verifiable data are missing, such as:

- Maximum dimensions
- Volume
- Climatic values
- Accuracy for the qualification



Overloaded Cabinet – Fan obstructed










Calculate the size:

- Long-term stability test 25 °C / 60 % rel. humidity (24 months storage)
- Accelerated stability test 40 °C / 75 % rel. humidity (6 months storage)

Determination of the size:


Selection of 6 test room volumes: from 210 – 1700 litres, otherwise chambers







Lifetime costs of ownership:





PRODUCT SELECTION

Walk-in rooms:

1

- Small rooms are inefficient
- Optimal solution: Shelves on both sides, if possible, depth 60 cm and aisle width 80 cm
- Shelve width for solids 130 cm and for liquids 90 cm (weight!) because of boxes 60 x 40 cm





RUMED[®]

Rubarth Apparate GmbH



Installation in a Clean Room

- Integration of the units in a clean room partition wall
- Operation and charging are done from the clean room
- Service and maintenance from outside the clean room



PRODUCT SELECTION

Installation in a Clean Room

Direct installation of the equipment in the clean room

1

Water-cooled refrigerating machine (no fin heat exchanger with fan because of the particle swirl)









Requirements, Regulations & Documentation:

User Requirements:

- Volume
- Geometry
- Equipment
- Materials
- Calibration
- Qualification
- Bringing in
- Regulations (such as VDE, UVV, CE, Regulation for Workplaces)

- Documentation
 - Qualification File
 - Technical Plans
 - Bill of Materials of Electrical and Mechanical Components
 - Wiring Diagram
 - Operating Manuals
- Deviations
- If applicable Layout of the installation place

Differentiation in must criteria, target criteria and can criteria



Transport/Placement

Components can be removed easily for displacement through doors and placement in lifts

Advantage:

- Even larger appliances can be displaced
- Thus, the components are easily accessible for maintenance tasks





Space Saving

- The width of the doors does not exceed the units' width.
 - Advantage: space-saving side-by-side installation.
- Minimum lateral distance to the wall or distance between the appliances



Media Connections:

Electricity

- Pure water
- Condensate Drain
- Heat dissipation into the room (not every room is suitable)
- If required, cooling water (water-cooled unit)





Functional Specification

FDS (Functional Design Specification) "realization requirements developed by the contractor for realization of the principal's requirements specification"

Proposed solutions of the supplier using the example of the media connections (water connection):

- Direct connection pure water to the conduit system
- Ion exchanger to the drinking water connection
- Canister for installation places without water connection
- Canister with float switch







Functional Specification

Proposed solutions of the supplier using the example of the media connections (condensate drain):

- Condensate drain fixed pipe connection
- Lifting pump for higher situated sewage pipes
- Heated evaporation pan, if sewage water connection does not exist (automatic emptying)
- Collecting vessel



Rubarth Apparate GmbH







Waste Heat:

Refrigerating Machine



Refrigerating machine in the installation room (possibly cooling of the emitted heat is required)

Outdoor Installation




 Outdoor installation of the refrigerating machine (for chambers)

Water Chiller



 Water-cooled unit (cooling water of the customer)






Comparison URS with the Supplier's Offer (FDS) according to the DQ Plan

For Stability Test Chambers:

- Drawing for approval
- Final dimensions
- Required distances
- Media connections
 (location + dimension)





Preparation of a Time Schedule

- Possibilities of delivery and unloading
- Access authorization of the service technicians
- Working hours









Qualification & Calibration

Traceability guaranteed



Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 22 / 45





From the DQ to the PQ

- Plants / Units for the pharmaceutical industry are subject to the qualification obligation
- Requirements are defined in GLP / GMP / ISO 9000
- Evidence of the suitability for the intended use
- The responsibility is incumbent on the operator

Design Qualification (DQ)



Performance Qualification (PQ)

Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 24 / 45

The Process of Equipment Qualification

- Factory Acceptance Test (FAT)
- Design Qualification (DQ)
- Installation Qualification (IQ)
- Operation Qualification (OQ)
- Performance Qualification (PQ)
- Maintenance Qualification (MQ)





Manufacturer's Site

On site

2 QUALIFICATION

Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 25 / 45

Qualification by the Manufacturer

- Reduction of the qualification phase of 3 weeks to 3 days
- Time-saving and cost-efficient due to many years of experience
- Prepared records
- Approved test methods, such as for the alarms
- Device-specific knowledge
- Training certificate for the users
- Test report for the final unit release







Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 26 / 45

Design Qualification

Documented Evidence:

- The appliance complies with the company requirements, and you get exactly what you need
- The functional and operational specifications of the appliance are determined
- The choice of a supplier is explained





QUALIFICATION



Installation Qualification

Documented Evidence:

- The delivered appliance complies with the specifications (DQ) of the order
- Complete and undamaged delivery
- Correct execution of the installation at the intended location
- Correct design concerning the environmental conditions at the installation place




RUMED

Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 28 / 45

Operation Qualification

- Documented evidence, that the installed appliance works according to its specifications
- The appliance works under the companies' environmental conditions at the predetermined location.
- Verification of the distribution in space in the empty appliance
- Mapping in the appliance centre and in the 8 corners of the appliance
- All sensors must be within the range





Aspects of the ICH-compliant storage for stability tests 29 / 45

Performance Qualification

- Documented evidence of constant performance under real operating conditions
- Mapping of the temperature distribution and humidity distribution in space in loaded condition
- Sensors must have a valid certificate and must be traceable to national standards (DKD, SCS, ÖKD)
- Photograph of loading conditions
- Optionally: Open door study
- Important: Ensure sufficient loading for realistic PQ mapping







Maintenance Qualification

- Documented evidence, that the appliance is maintained correctly and according to the specifications to ensure continuous operation
- Determination of cleaning intervals
- Determination of service intervals (maintenance contract)
- Recalibration (PQ)







Monitoring and Failure Management

21CFR part 11 compliant


RCS 4.0 - RUMED Control2015.touch - Übersicht ...



Aspects of the ICH-compliant storage for stability tests 31 / 45




Data Recording + Alarms



Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 32 / 45





Laboratory Book

- Only 1 working value
- Reading errors and transmission errors are possible
- Time-consuming
- High error rate in reading/ transmission



Data Logger

- Subsequent evaluation
- Risk of confusion in case of many measuring points
- Recognition too late

LG 186 - Klimaschrank (30°C / 65%)	LG 187 - Klimaschrank (30°C / 75%)
	L
* 🌡 🐃 29.9 m * " 300 m	* \$ *** 30.1 * * ** 30.0
• • • 65.0 s • • 65.0 s	• * *** 75.0 s • ** 75.0
LG 199 - Kilmaschrank BTM (30°C / 65%)	LG 200 - Klimaschrank BTM (40°C / 75%)
	1 (C) (Name and a second secon
* 1 ··· 30.0 ·c · ·· 300 ·c	* i = 40.0 ~ * ac
* *** 55.5 x # 450 x	75.0 s ** m
	(30°C / 65%)

Software

- Raw data are archived
- Current history display by means of graph recorder
- Less manual expenditure
- Digital signature possible
- Logbook firmly linked to graph representation

Media Outage (Water, Electricity, etc.)

The following parameters should be recorded during monitoring:

Temperature

Profile Humidity

Profile logbook with:

Messages with time-stamp, such as:

- User Login / Logout
- Changes of Target Values
- Digital Signature
- Door Opening
- Expired Maintenance Interval

Messages with time-stamp, such as:


- Excess temperature and insufficient temperature
- Humidity value too high or too low
- Conductivity of the humidifier water too high
- Chiller shut-down in case of low pressure or overpressure
- Sensor failure

3 OPERATION

RUMED[®] Rubarth Apparate GmbH

Integrated Screen Recorder

- Recording of actual values of all regulator and control circuits.
- For clearness, all channels can be shown or hidden.
- Past periods can be scrolled conveniently page-by-page.
- Even with power failure, a restricted, battery backed monitoring is effected.



3 OPERATION



Logbook

- Gapless event documentation in real time, inseparably connected with the recorded data.
- Filter function for the quick, selective display of the events.
- Free comments with login name are possible at any time.

$\bigcirc \leftarrow$ Logbool	x 16.07.2015 17:03:30	frey 👤
Date	Message	All 🛛 🏹
16.07.2015 08:04:23 Uhr	Door open	Note
16.07.2015 08:05:34 Uhr	- Door closed	Note
16.07.2015 08:30:02 Uhr	Door open	Note
16.07.2015 08:32:21 Uhr	- Door closed	Note
▼ 16.07.2015 14:02:45 Uhr	Interior had been cleaned (frey)	Comment
16.07.2015 16:59:29 Uhr	Door open	Note
16.07.2015 17:00:29 Uhr	- Door closed	Note
▼ ▲	from 21.06.15 ► to 16.07.15 ► to 16.07.15 ►	÷

Comment Entry

- Complete keyboard for entry of comments into the logbook and for entry of individual names for program creation.
- The assignment of the keys is adapted automatically to the selected language.

	\leftarrow	Log	bo	ok					16.0	7.20)15	17	:06:3	30				frey 🚺
Please	Please enter the comment																	
Inter	Internal Audit successfully completed Save Cancel																	
+%°		1	2		3	4	•	5	6		7		8		9	0]
Q	W	E		R	T		Ζ	U	I	I		0		Ρ	1	Ü	<	Х
A		S	D		F	G		H	J		Κ		L		Ö	Ä		↵
↑	Y	X		С	V	,	В	Ν	I	Μ		,		•		_	1	`
																	l	►

Calendar

- The calendar function allows quick direct access to past recording periods - no matter if to the recorder, to the logbook or for data export.
- All days, for which data have been recorded, are colour-highlighted.

$\hat{\Box} \leftarrow Re$	ecorder		16.07.	frey 🚺		
		•	July 2015	•		Today
Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
29	30	31	01	02	03	04
05	06	07	08	09	10	11
12	13	14	15	16	17	18
19	20	21	22	23	24	25
26	27	28	29	30	31	01
Hour 1/	′2 Day [Day W	eek ┥	10.07.15 16.07.15		Le Log



Digital Signature

- Signature of the checked periods directly at the recorder of the control in conformity with 21CFR part 11.
- Undersigned areas are marked correspondingly in the recorder.


\bigcirc \leftarrow Recorder	16.07.2015 22:20:35	blume 🚺
blume	Create signature for the period 16.07.2015 00:00-22:20 Uhr	• 2.
	Cancel Yes	

3 OPERATION

RUMED[®] Rubarth Apparate GmbH

User Login

- In the user management, the preferred language can be assigned to the users. A quick change is possible at any time.
- Thanks to the user management, the activities of each user can be traced exactly.
- In connection with the option Electrical Door Release, even the door opening can be allocated to a user.



3 OPERATION

RUMED[®] Rubarth Apparate GmbH

User Management


- The user management can be customized: It can be deactivated completely, or different rights can be allocated to the users.
- Passwords can be restricted in time, and the access can be locked after a defined number of failed login attempts.
- The user management allows the use of the appliance in conformity with 21CFR part 11.

\square	User Managei	nent 16.07.2	015 15:06:40	Log-in 👤			
U	ser ID	First Name/Name	Capacity	Status	Created on		
b	lume	Anna Blume	Laborant	new	01.08.2014		
fe	ernandez	Sylvia Fernadez	Laborant	blocked	28.08.2014		
k	lose	Richard Klose	QT	inactive	02.02.2015		
_ v	/immer	Erwin Wimmer	Leitung	active	20.05.2015		
f r	rey	Otto Frey	Laborant	active	19.06.2015		
	′ A	New	Сору	ĺ	Edit		





The worst that can happen is sample loss









3 OPERATION

RUMED[®] Rubarth Apparate GmbH

Failure Management

- Early recognition of a failure allows short reaction times of the user
- Redundant chambers
- Rearrangement into a back-up appliance Service manual + training
- Stockpiling of important spare parts



3 OPERATION

Possible Measures in Case of Failure

Excess temperature: Emergency cooling with tap water

Humidifier failure: Emergency humidification by evaporation humidifier with hygrostat

Power failure:

SOP:

Rechargeable battery for 24 h data recording for retrospective risk assessment (deviation report)

Action plan for failures









Thank you very much for your attention

Do you have any questions? www.rumed.de/en/downloads/vortraege

Dipl.-Ing. Volker Rubarth | Manager, Rubarth Apparate GmbH

Aspects of the ICH-compliant storage for stability tests 45 / 45